

**ADVERTISEMENT FOR BIDS
For the Construction of:**

**Pecos WWTP Lagoon Abandonment Plan
Pecos, New Mexico**

Sealed bids will be received at 92 Main St. Pecos, NM 87552 for the project described below no later than 11:00 am local time, 01/26/2022. The public opening and reading of bids will commence after close of bid time at this location. Delivery of bids to the Village of Pecos is the sole responsibility of the Bidders.

Plans, specifications, and other contract documents may be obtained over the internet at <http://www.wilsonco.com/bid-documents>. It is the plan holder's sole responsibility to obtain any addendums posted to this site prior to bid.

A Non-mandatory Pre-Bid conference will be held at 11:00 am on 01/19/2022, at 92 Main St., Pecos, NM 87552. Attendance by contractors intending on submitting a bid is non-mandatory in accordance with Instructions to Bidders. Suppliers or subcontractors are encouraged but not required to attend.

Description of Project: The Pecos WWTP Lagoon Abandonment Plan consists of earthwork, as well as demolition and disposal of sludge material. The selected bidder will be responsible for the temporary removal of all sludge from the Lagoons. The bids for this project will be evaluated on the total cost for the Base Bid + Additive Alternate A. Any off-site hauling/disposal will require coordination with the property owner as shown in the plans.

Base Bid: The base bid for this project consists of the removal of 860 Cubic yards of sludge from Lagoon #2. All sludge will be removed from the lagoon and disposed in a landfill licensed to accept the material. All sludge must pass the paint filter test prior to delivery to the landfill.

Additive Alternate A: The base bid for this project consists of the removal of 4436 Cubic yards of sludge from Lagoon #3. This additive alternate is broken into lots, with the intent to remove as much sludge as possible within the project budget. All sludge will be removed from the lagoon and disposed in a landfill licensed to accept the material. All sludge must pass the paint filter test prior to delivery to the landfill.

Additive Alternate B: This alternate includes 3817 Cubic Yards of grading in Pond 3. The pond liner in Pond 3 shall be removed and disposed of at an appropriate landfill. The pond bottom shall be graded such that there is no pooling to ensure positive drainage within the lagoon area.

Additive Alternate C: This alternate includes 4910 Cubic Yards of grading in Pond 2. The pond liners shall be removed and disposed of at an appropriate landfill. The contractor shall remove all structures within the lagoons, including the lagoon aerators and associated wiring and any piping, as well as the concrete aerator removal structure and crane; the Existing concrete Chlorination Box will be removed as well. The pond bottom shall be graded such that there is no pooling to ensure positive drainage within the lagoon area.

Advertised in:
Albuquerque Journal,
Santa Fe New Mexican

Advertising dates: 01/10/2022 & 01/14/2022

For: Village of Pecos
By: Wilson & Company, Inc.
Date: 01/07/2022
Phone number: (505) 757-6591