

**ADVERTISEMENT FOR BIDS
For the Construction of:**

**Pecos WWTP Lagoon Abandonment Plan
Pecos, New Mexico**

Sealed bids will be received at 92 Main St. Pecos, NM 87552 for the project described below no later than 11:00 am local time, 1/29/2021. The public opening and reading of bids will commence after close of bid time at this location. Delivery of bids to the Village of Pecos is the sole responsibility of the Bidders.

Plans, specifications, and other contract documents may be obtained over the internet at <http://www.wilsonco.com/bid-documents>. It is the plan holder's sole responsibility to obtain any addendums posted to this site prior to bid.

A Mandatory Pre-Bid conference will be held at 11:00 am on 1/22/2021, at 92 Main St., Pecos, NM 87552. Attendance by contractors intending on submitting a bid is mandatory in accordance with Instructions to Bidders. Suppliers or subcontractors are encouraged but not required to attend.

Description of Project: The Pecos WWTP Lagoon Abandonment Plan consists of earthwork, as well as demolition and disposal of sludge material. The selected bidder will be responsible for the temporary removal of all sludge from the Lagoons. Once all sludge is removed and stockpiled on site, the contractor will be responsible for testing of sludge to verify that the sludge meets "Class A" requirements, any sludge that does not meet the requirements for "Class A" Sludge is to be removed and disposed of in a landfill that can accept this material; preliminary testing has indicated that the sludge in the lagoons meets "Class A" requirements. All sludge meeting "Class A" requirements may be land applied within village limits, with application rates to be verified by the Engineer prior to delivery; the village will identify private property owners that are willing to accept the sludge for beneficial use. All remaining sludge shall be disposed of in a landfill that is licensed to accept the material, all sludge must pass the paint filter test prior to delivery. Any off site hauling/disposal will require coordination with the property owner as shown in the plans. The contractor shall remove all structures within the lagoons, including the lagoon aerators and associated wiring and any piping, as well as the concrete aerator removal structure and crane. The Existing concrete Chlorination Box will be removed as well. The pond liners shall be removed and disposed of at an appropriate landfill. The lagoons shall be graded as shown in the plans. Site grading consists of 4,615 CY of grading, no import of fill will be required for this project. The pond bottom shall be graded such that there is no pooling to ensure positive drainage within the lagoon area.

The requirements for bidders and contractors under this order are explained in the specifications.

Advertised in:
Albuquerque Journal,
Santa Fe New Mexican

Advertising dates: 1/11/2020, 1/18/2020

For VILLAGE OF PECOS
By: Telefon A. Benavides 01/07/20
Date
Phone number (505) 757-6591